

FED. ROAD DIST. NO.	STATE	PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	HIA-01-98M	1998	3	11

GENERAL NOTES

1. The scope of work for this project consists of sealing deck cracks; reconstructing structure approaches with asphalt concrete; and installing pavement striping, marking and signs.
2. The Contractor is reminded of the requirements of Subsection 108.01 - Subletting of Contract, which requires him to perform work amounting to not less than 50 percent of the total contract cost less deductible items. Non-compliance with this Subsection may be grounds for rejection of bid.
3. The Contractor's attention is directed to the following Sections of the Special Provisions : Subsection 107.13 - Public Convenience and Safety; Subsection 107.21 - Contractor's Responsibility For Utility Property And Services; and Section 645 -Traffic Control.
4. At the end of each day's work, the Contractor shall remove all equipment and other obstructions to permit free and safe passage of public traffic.
5. Existing pavement markers and striping on the deck shall be removed and disposed of prior to the epoxy application.
6. The Contractor shall notify the State in writing, two (2) weeks prior to construction.
7. Smooth riding connections shall be constructed at all limits of paving.
8. Dressing of shoulder shall consists of clearing and grubbing, and compacting with suitable material as directed by the Engineer. This work shall be considered incidental to asphalt concrete.
9. The Contractor shall obtain a street usage permit from the City and County of Honolulu, Department of Transportation Services two (2) weeks prior to construction, informing them of location, scope of work, and closure of Farrington Highway and/or traffic lanes and dates of closure.
10. The Contractor shall notify the Oahu Transit Services, Inc's Lowell Tom (848-4578) or Ed Sniffen (848-4571), two (2) weeks prior to construction, informing them of location, scope of work, and closure of Farrington Highway and/or traffic lanes and dates of closure.
11. The construction signs shall become the property of the Contractor at the completion of the project.

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	DESIGNED BY	
	CHECKED BY	
NOTE BOOK	DATE	
	BY	
	BY	
	BY	

STATE OF HAWAII	
DEPARTMENT OF TRANSPORTATION	
HIGHWAYS DIVISION	
GENERAL NOTES	
Interstate Route H-1	
Farrington Highway Separation	
Seal Deck Cracks	
Project No. HIA-01-98M	
Scale: None	Date: April, 1998
SHEET No. 1 OF 1 SHEETS	