

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

ADDENDUM NO. 2

FOR

INTERSTATE ROUTE H-1 FREEWAY

LIGHTING SYSTEM RECONDUCTORING

MAKAKILO INTERCHANGE TO KUNIA INTERCHANGE

PROJECT NO. H1A/D-01-10M

DISTRICT OF EWA

ISLAND OF OAHU

FY 2011

The following amendments shall be made to the Bid Documents:

A. SPECIFICATIONS

- a. Amend Subsection 622.02 – Materials, by adding the following paragraph after line 47:

“Anchor bolts, nuts and washers for conduit bracket connections to concrete structures shall be stainless steel Type 316 as shown on the structural drawings.”

B. PROPOSAL SCHEDULE

- a. Replace pages P-10 and P-11 dated 08/12/10 with the attached pages P-10 and P-11 dated r12/03/10.

C. PLANS

- a. Amend Plan Sheet No. 37 by revising General Structural Note No. 5 to read as follows:

“5. Anchor bolts into existing concrete structures shall be undercut type of anchor bolts. All anchor bolts, nuts and washers shall be Stainless Steel Type 316. Acceptable product is “HAD-P” by Hilti Corp., or approved equal.”

Please acknowledge receipt of this Addendum No. 2 by recording the date of its receipt in the space provided on page P-4 of the Proposal.



for

MICHAEL D. FORMBY
Interim Director of Transportation

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX QUANTITY	UNIT	UNIT PRICE	AMOUNT
209.1001	Installation, Maintenance, Monitoring, and Removal of BMP	L.S.	L.S.	L.S.	\$ _____
209.1002	Additional Water Pollution, Dust and Erosion Control	F.A.	F.A.	F.A.	\$ <u>25,000.00</u>
622.1001	3#2 XHHW and #2 Ground Conductors	L.S.	L.S.	L.S.	\$ _____
622.1005	Street Light Standard Including Removal of Exist Concrete	L.S.	L.S.	L.S.	\$ _____
622.1011	Provide Pullbox Cover	L.S.	L.S.	L.S.	\$ _____
622.1012	Expose Dirt Covered Pullbox	L.S.	L.S.	L.S.	\$ _____
622.1015	Replace 250 Watt High Pressure Sodium Lamps	L.S.	L.S.	L.S.	\$ _____
622.1020	Replace Identification Tag	L.S.	L.S.	L.S.	\$ _____
622.1025	Provide 3#8 Conductors and Fuseholders	L.S.	L.S.	L.S.	\$ _____
622.1030	12" X 16" X 6" NEMA 4X Junction Box	L.S.	L.S.	L.S.	\$ _____
622.1040	1-2 Inch PVC Coated Galvanized Rigid Steel Conduit and Mounting Brackets	L.S.	L.S.	L.S.	\$ _____
622.1050	Remove 3#2 & #6 Ground Conductors	L.S.	L.S.	L.S.	\$ _____
622.1060	Remove 2-2 Inch PVC Coated Galvanized Rigid Steel Conduit and Mounting Brackets	L.S.	L.S.	L.S.	\$ _____
622.1080	Replace Damaged Underground 1-2 Inch Street Light Conduit	F.A.	F.A.	F.A.	\$ <u>25,000.00</u>

PROPOSAL SCHEDULE

ITEM NO.	ITEM	APPROX QUANTITY	UNIT	UNIT PRICE	AMOUNT
622.1090	Replace Damaged Luminaires	F.A.	F.A.	F.A.	\$ <u>7,500.00</u>
645.1001	Traffic Control	L.S.	L.S.	L.S.	\$ _____
645.1002	Additional Police Officers, Additional Traffic Control Devices and Advertisement	F.A.	F.A.	F.A.	\$ <u>25,000.00</u>
648.0100	Field-Posted Drawings	L.S.	L.S.	L.S.	\$ _____
699.1000	Mobilization (Not to exceed 10% of the sum of all items excluding the bid price of this item and force account items)	L.S.	L.S.	L.S.	\$ _____

SUM OF ALL ITEMS..... \$ _____

NOTE: Bidders must complete all unit prices and amounts. Failure to do so may be grounds for rejection of bid.