

ORIGINAL PLAN
DATE
SURVEY PLOTTED BY
DESIGNED BY
NOTE BOOK
QUANTITIES BY
CHECKED BY
N. 11/26/2010

GUARDRAIL SCHEDULE				
LOCATION	Item No. 606.3110 Guardrail, Type 3- Single with Steel Post	Item No. 606.3500 Guardrail, Type 3- Triple Beam with Steel Post	Item No. 606.3510 Guardrail, Type 3- Double (Nested) Triple Beam with Steel Post	Item No. 606.7010 Terminal Section, Type BCT
INBOUND	L.F.	L.F.	L.F.	Eq.
Sta. 260+16± to Sta. 261+00 Rt.	50	21.50	12.50	
Sta. 265+50 to Sta. 266+34± Rt.	50	34		
Sta. 276+50± to Sta. 278+40 Rt.	131	21.50	12.50	1
I.B. Sta. 298+50 to Sta. 309+00± Rt.	1,016	34		
I.B. Sta. 309+00± to Sta. 313+00± Rt.	400			
I.B. Sta. 317+50± to Sta. 325+00± Rt.	725			1
OUTBOUND				
O.B. Sta. 208+20± to Sta. 210+00 Lt.	146	34		
O.B. Sta. 220+00 to Sta. 220+84± Lt.	50	21.50	12.50	
Sta. 265+50 to Sta. 266+34± Lt.	50	21.50	12.50	
Sta. 270+00± to Sta. 271+50 Lt.	116	34		
Sta. 273+50 to Sta. 278+22.18 Lt.	404	55.50	12.50	
Sta. 290+00 to Sta. 295+00± Lt.	466	21.50	12.50	
Sta. 297+16± to O.B. Sta. 298+00 Lt.	50	34		
O.B. Sta. 310+00 to Sta. 310+84± Lt.	50	21.50	12.50	
O.B. Sta. 317+00± to Sta. 322+00 Lt.	466	34		
O.B. Sta. 329+50 to Sta. 330+84± Lt.	100	21.50	12.50	
TOTAL	4,270	410.00	86.00	2

CONCRETE BARRIER AND GLARE SCREEN SCHEDULE				
LOCATION	Item No. 606.4160 Guardrail, Type 4E - Concrete Median Barrier	Item No. 606.4170 Guardrail, Type 4F - Concrete Median Barrier	Item No. 606.8200 Concrete Glare Screen on Existing Median Barrier	Item No. 202.0420 Removal of Existing Concrete Median Barrier
	L.F.	L.F.	L.F.	L.F.
Sta. 191+05± to Sta. 192+33±	128			
Sta. 192+33± to I.B. Sta. 198+75±		642		
I.B. Sta. 198+75± to Sta. 200+00±	125			
I.B. Sta. 200+00± to Sta. 207+38±		738		
I.B. Sta. 207+38± to Sta. 211+30±	392			
I.B. Sta. 211+30± to Sta. 216+00±		470		
I.B. Sta. 216+00± to Sta. 224+58±	858			
I.B. Sta. 215+00 to Sta. 224+58±				958
I.B. Sta. 224+58± to Sta. 246+66±			2,024	
Sta. 246+66± to Sta. 255+40	874			874
Sta. 255+40 to I.B. Sta. 302+20			4,680	
O.B. Sta. 343+20 to Sta. 368+80				2,583
O.B. Sta. 343+00 to Sta. 349+50±		650		
O.B. Sta. 349+50 to Sta. 368+80±	1,933			
TOTAL	4,310	2,500	6,704	4,415

- NOTES: 1. Removal and hauling of existing headlight glare screen will be incidental to Item No. 606.8200-Concrete Glare Screen on Existing Median Barrier. Removed headlight glare screen shall be hauled to Highways Division, Pearl City Baseyard as directed by the Engineer.
2. Refer to Plan Sheet No. 89 for Concrete Barrier and Glare Screen details.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	IR-H2-1(27)	1992	24	223

REMOVAL OF EXISTING METAL GUARDRAIL SCHEDULE	
LOCATION	LENGTH
INBOUND	L.F.
Sta. 277+50± to Sta. 287+50± Rt.	1,000
I.B. Sta. 298+00± to Sta. 311+50± Rt.	1,350
OUTBOUND	
Sta. 257+50± to Sta. 259+70± Lt.	220
Sta. 271+00± to Sta. 293+30± Lt.	2,230
Sta. 297+30± to O.B. Sta. 310+50± Lt.	1,320
O.B. Sta. 318+50± to Sta. 330+80± Lt.	1,230
TOTAL	7,350

NOTE: Removal and disposal of existing metal guardrail will be incidental to Item No. 606.3110-Guardrail, Type 3-Single with Steel Post.

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GUARDRAIL SCHEDULE

INTERSTATE RTE. H-2, HOV LANES, PH. II
Millian Interchange to Waipio Interchange
F.A.I. PROJECT NO. IR-H2-1(27)

Date: April, 1992

SHEET No. 1 OF 1 SHEETS