

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-H2-1(034)R	2022	3	32

- | | | |
|--|-------------------------|------------|
| ORIGINAL
PLAN | SURVEY PLOTTED BY _____ | DATE _____ |
| NOTE BOOK

<i>ddxx</i>
<i>xxdgn</i>
N _o . | DRAWN BY <i>x</i> | * |
| | TRACED BY _____ | * |
| | DESIGNED BY <i>x</i> | * |
| | QUANTITIES BY _____ | * |
| | CHECKED BY _____ | * |

INTERSTATE ROUTE H-2, PCCP REHABILITATION

(NORTHBOUND), AT VARIOUS LOCATIONS

FEDERAL AID PROJECT NO. NH-H2-1(034)R

Scale: NONE Date: Feb., 2022

SHEET No. 1 OF 2 SHEETS

GENERAL NOTES - Cont.

28. All existing right-of-way, centerline, as-built, construction, and NGS (horizontal and vertical in the NGS database) monuments located within the State of Hawaii right-of-way, must be preserved and displayed on the plans. All monuments shall be preserved during all design and construction phases. If monuments are disturbed or destroyed, the Cadastral Engineering Section (HWY-DC) shall be notified prior to groundbreaking. Reconciliation to the Right-of-Way Baseline and/or a boundary study and determination may be required prior to re-installation of the disturbed or destroyed monuments. HWY-DC shall be contacted for guidelines and procedures. As to construction, a State of Hawaii Licensed Surveyor shall perform the location and staking of the reset monument. The DOT Standard Plans and Specifications, with the exception of NGS monuments which shall have a NGS approved "brass disk" marker, shall be referenced for the monument type and materials.

Any NGS vertical monuments that are deemed necessary for relocation due to construction shall follow the NGS benchmark reset procedures written by Curtis Smith dated September 2010 or newer. All work must be done by an electronic digital level that is acceptable by NGS for second-order class one or higher work. The surveyor must use two one-piece invar barcode rods with current certifications with struts with 15 lbs turning plate or turtles; and/or turning pin with driving cap and temperature readings. Contact NGS prior to any work to ensure all equipment meets reset specifications. A State of Hawaii Licensed Surveyor shall perform the relocation. All work must be submitted both in electronic and hard copy formats to NGS and HWY-DC.

All monument work shall be considered incidental to this project.

FED. ROAD DIST. NO.	STATE	FED. AID PROJ. NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
HAWAII	HAW.	NH-H2-1(034)R	2022	4	32

ORIGINAL PLAN	SURVEY PLOTTED BY	DATE
	DRAWN BY	
	TRACED BY	
	DESIGNED BY	
	CHECKED BY	
NOTE BOOK		
DATE		
NO.		

STATE OF HAWAII
DEPARTMENT OF TRANSPORTATION
HIGHWAYS DIVISION

GENERAL NOTES AND LEGEND

INTERSTATE ROUTE H-2 PCCP REHABILITATION
(NORTHBOUND) AT VARIOUS LOCATIONS

FEDERAL AID PROJECT NO. NH-H2-1(034)R

Scale: NONEDate: Feb., 2022

SHEET No. 2 OF 2 SHEETS