



Aluminum railing concrete parapet & end post to receive "Class 2 Surface Finish."

ITEM	DESCRIPTION	ALLOY	UNIT PRICE
Top Rail	Al Alloy Drawn Or Extruded Tube 4" o.d. x 1/4" thick wall.	6061 - T6	1.70 */ft.
Bot. Rail	Al Alloy Drawn Or Extruded Tube 3 1/2" o.d. x 1/8" thick wall.	6061 - T6	1.56 */ft.
* Rail Post	Alcoa No. 2001 Permanent Mold Casting or approved equal.	Post 356-T6 Bot Sc. 2024-T4	160 */ea.
Rail Cap	Alcoa No. 3C5 4-7/8" (Top Rail) and Alcoa No. 3C5 3-1/2" (Bot. Rail) or approved equal.	Cap 356-T6 Bot Sc. 2024-T4	Top - 4.15 */ea. Bot. - 3.40 */ea.
Bolts	Alcoa No. 33-1175 or approved equal with hexagon nut and plain washer.	Bolt 2024-T6 Nut 6061-T6 Washer 2024-T6	—

LIGHT STD. BASE REINF. DETAIL

STANDARD DETAILS

MDANALLIA RD. ~ PROJ. NO. S-0720(1) - UNIT 2
SCALE AS NOTED

SHEET No. 1 OF 1 SHEETS