SECTION 634 – PORTLAND CEMENT CONCRETE SIDEWALKS

Make the following amendment to said Section:

(I) Amend **Section 634.04 - Measurement** by replacing lines 60 to 61 to read:

"**634.04 Measurement.** The Engineer will measure Portland cement concrete sidewalks by the square yard of finished surface."

(II) Amend **Section 634.05 – Payment** by replacing lines 62 to 72 to read:

"**634.05 Payment.** Payment will be full compensation for work prescribed in this section and contract documents.

The Engineer will pay for following pay item when included in proposal schedule:

Pay Item	**Pay Unit**
Portland Cement Concrete Sidewalk	Square Yard

The Engineer will pay for excavation of unsuitable material and backfill with material acceptable to the Engineer under Section 203 – Excavation and Embankment. If no pay item exists, refer to Subsection 104.02 – Changes."

END OF SECTION 634