

1 **SECTION 645 – WORK ZONE TRAFFIC CONTROL**

2
3 Make the following amendments to said Section:

4
5 **(I)** Amend **Subsection 645.02 Materials** by revising the section from line 39
6 to 48 to read:

7
8 “Submit at least 30 working days before work starts, 3 sets of FHWA
9 approval letters certifying compliance with MASH for signs, sign supports,
10 barricades, delineators, cones, vertical panels, concrete barriers with
11 MASH end treatments, and other traffic control devices. Use of signs sign
12 supports, barricades, delineators, cones, vertical panels, and other traffic
13 control devices will not be allowed.

14
15 Furnish to Engineer at least 30 working days before work starts, self-
16 certified MASH compliant letter from vendor for each type of Category 1
17 traffic control device, as defined in MASH, including single-piece traffic
18 cone, single-piece drum, tubular marker, and delineator.”

19
20 **(II)** Amend **Subsection 645.03(C)(1) General** by revising the section from
21 line 188 to 190 to read:

22
23 “Do not install signs on barricades unless signs and barricades have been
24 crash tested as a unit and accepted under MASH.”

25
26 **(III)** Amend **Subsection 645.03(F) – Lane Closures** by revising the section
27 from line 248 to 252 to read:

28
29 **“(F) Lane Closures.** Exceptions to lane closure hours specified require
30 written acceptance by the Engineer. No increase in contract price or
31 contract time will be given for lane closure restrictions specified.

32
33 **(1) Shoulder Lane Closures.** Shoulder lane closures are
34 allowed during working hours.

35
36 **(2) Nighttime Work Maintaining Two (2) Through Lanes.**
37 Nighttime lane closures that maintain a minimum of two (2)
38 through lanes in a particular direction (i.e., eastbound or
39 westbound) will be allowed during the following hours:

40
41 Sunday Night to Friday Morning 9:00 p.m. to 4:00 a.m.

42
43 **(3) Nighttime Work Maintaining One (1) Through Lane.**
44 Nighttime lane closures that maintain a minimum of one (1)
45 through lane in a particular direction (i.e., eastbound or
46 westbound) will be allowed during the following hours:

47
48 Monday to Friday 11:30 p.m. to 4:00 a.m.

The Contractor shall not close both Eastbound and Westbound lanes simultaneously or consecutive on/off ramps.”

(IV) Amend **Subsection 645.03(F) – Lane Closures** line 277 to 279 to read as follows:

“At the Engineer’s discretion, with a one week prior notification to the Contractor, work may be suspended to allow traffic to flow freely during major public events, such as concerts, parades, sporting events, etc. The Contractor will not be compensated but the Contractor’s Roadway Completion Time and/or Contract Time will be adjusted accordingly.

The Engineer may also suspend work at any time due to unforeseen circumstances that occur within the immediate vicinity that may disrupt the traffic on the freeway and/or alternate routes or in times of emergencies.”

(V) Amend **Subsection 645.03 – Construction** by adding the following after line 395:

“(I) – Variable Message Sign. Furnish, install, maintain and remove variable message sign at locations and durations as specified in the Signing and Pavement Marking Plans and Traffic Control Plans.”

(VI) Amend **Subsection 645.05 – Measurement** by revising the section from line 417 to 420 to read:

“Construction Warning Signs	Lump Sum
Type II Barricades	Lump Sum
Cones	Lump Sum
Arrow Board Panel	Lump Sum
Additional Police Officers	Force Account
Additional Traffic Control Devices	Force Account
Advertisement	Force Account”

END OF SECTION 645