

1                                   **SECTION 641 – HYDRO-MULCH SEEDING**

2  
3       Make the following amendments to said Section:

4  
5       **(I)**     Amend **Subsection 641.02(B) – Fertilizer** by revising the section from  
6       line 33 to 36 to read:

7  
8               **“(B) Fertilizer.**   Proper fertilizer shall be used in hydro-mulch mix,  
9               depending on condition of soil. Apply at rates and in amounts consistent  
10              with manufacturer’s specifications. Contractor shall provide a Soil Analysis  
11              Report, if requested by Engineer, and shall use report to determine  
12              quantity and ratio of fertilizer for sustained growth of grass. Submit  
13              recommendations from a licensed Landscape Architect when deviating  
14              from the application rates and amounts above.”

15  
16  
17       **(II)**    Amend **Subsection 641.03(A) – Seeding** by revising the first paragraph  
18       from line 100 to 103 to read:

19  
20               **“(A) Seeding.**   Apply seeded mulch within the timeframe in Subsection  
21              209.03(B) – Construction Requirements, if temporary stabilization will not  
22              be utilized, after completion of slopes or portion of slope when exposed  
23              face attains height of 15 feet. Notify Engineer not less than 24 hours  
24              ahead of hydro-mulch seeding operation. Do not hydro-mulch until the  
25              Engineer inspects and accepts areas for planting.”

26  
27                                   **END OF SECTION 641**